


# KKT Training Series

The cBoxX Start-up Guide V2



# cBoxX Series Overview




**Front View**



**Electrical Cabinet**

**Compressor Compartment**

**Pump Compartment**



# | what to check before start-up

---

## **Before starting the chiller, we must check the following**


- Expansion tank nitrogen pressure
- Clean filter strainers after flushing the lines and after starting the chiller
- Verify correct piping diameter (Please refer to Installation Guidelines)
- Check phase rotation
- Air vents should be placed at the highest point of the water loop

# expansion tank

Check expansion tank nitrogen pressure with no glycol mixture in the system. Check with a tire pressure gauge.

## Tank Pressure

0.4- 0.6 Bar (5.8 – 8.7 PSI)






# strainers

Clean filter strainers before and after start-up procedure.



# phase rotation

Check for correct phase rotation to the chiller.



# air vents

Air vents should be placed at the highest point of the glycol loop.





## Start-up Procedure

- Static fill unit
- System start-up and air bleeding
- Operation
  - Glycol operation
  - Refrigeration operation
- Electrical
  - Amperage
    - Pump
    - Compressor
    - Fan
- Complete checklist




# static filling

Static filling for the chiller is done outside of the chiller. Can be read at the display screen of the chiller with compressor breakers powered off (see wiring diagram) .

## Static Fill Pressure


1.0 to 1.5 Bar (21.7 psi)



# system start-up and air bleeding

- Allow the pump to run for 15 seconds and turn it off again
- Open the air vents, purge the remaining air
- If the pressure drops. Fill again until the pressure with the pump OFF reaches 1.0 to 1.5 Bar
- Clean the filter strainer during the next-to last pass

If the pressure remains constant for 60 – 90 minutes of operation, proceed with chiller operation



# glycol operation


Power on chiller, pump should begin shortly.

## Operating Pressures (Glycol Circuit)

Coldwater Pressure: 1-2 Bar

Pump 1 Pressure Outlet: 5-6 Bar

**Tip: If pump pressure differential isn't 3-4 bar after pump start, check the following: Strainers/Closed Valves, Phase Rotation and Reversed Piping!**



# refrigeration operation

If heat load is present, the compressor will start.



## Operating Pressures (Refrigeration Circuit)

Low Pressure: 7-11 Bar

High Pressure: 28-31 Bar

## Chiller Set point

10 C





# Amperage

Amperage checks are done at the electrical cabinet (please use wiring diagram to identify the circuit).



## **Pump Amperage Average**

4-4.5

## **Compressor Amperage Average**

13-14

## **Fan Amperage Average**

.2-1.0


# connecting the remote panel

After completion of the start-up, the remote panel will need to be connected. Power must be off to perform the installation!



**Chiller**



Wired Supplied by KKT (Wire Label Number)	1	2	PE	3	4
Chiller Terminal Wire Block (X-4)	1	2	3	4	6
Remote Panel Wire Terminal Block (X-1)	1	2	3	4	5



**Remote Panel**

# activating the remote panel

Once the connections are made and verified we must energize the controller with the switch in the cabinet. Switch must be in the “OUT” position.



**Note:** Only one screen can be viewed while the chiller is in operation.

“IN” position = Screen viewed at chiller.

“OUT” position = Screen viewed at the remote panel.



# checklist



After verifying chiller operation, a checklist is completed.



☐ Startup  
☐ Preventative Maintenance  
☐ Service Work Order

**KKT chillers**

**Attention:** To avoid site issues, never turn off chiller without prior permission from site personnel.

**Site Information**

Site name:	Date:	(MM/DD/YYYY)
Site address:		
Technician:	SQ/PO#	
Equipment location:	Roof <input type="checkbox"/>	Same level <input type="checkbox"/>
Model:	Serial/produce:	
Was chiller operational upon arrival (Y / N)	If not, when was chiller returned to operation (Date / Time)	

Refrigerant type: R407C ☐ R134A ☐ R410A ☐ Other ☐

**Checklist**

	Yes	N/A	Yes	N/A
Buffer Tank Water Pressure (ECO only) <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Strainer in chiller and R/P cleaned <input type="checkbox"/>	<input type="checkbox"/>
Water quality checked <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Condenser coil clean and fins straight <input type="checkbox"/>	<input type="checkbox"/>
Water circuit checked for leaks <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Correct fan rotation <input type="checkbox"/>	<input type="checkbox"/>
Pump bearings / seals leak free <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Electrical connections tight <input type="checkbox"/>	<input type="checkbox"/>
Water circuit properly purged of air <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Relays replaced <input type="checkbox"/>	<input type="checkbox"/>
Obstructions above chiller <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Communication interface checked <input type="checkbox"/>	<input type="checkbox"/>
Min. 40 inch clearance around chiller <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Chiller operation checked using Eco Data logger <input type="checkbox"/>	<input type="checkbox"/>
Refrigeration piping checked for leaks <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Software version up to date <input type="checkbox"/>	<input type="checkbox"/>

**Electrical**

Incoming supply voltage:	L1 <input type="checkbox"/>	L2 <input type="checkbox"/>	L3 <input type="checkbox"/>	Crane case heaters operational <input type="checkbox"/>	<input type="checkbox"/>
Supply amperage:	L1 <input type="checkbox"/>	L2 <input type="checkbox"/>	L3 <input type="checkbox"/>	Remote display operational <input type="checkbox"/>	<input type="checkbox"/>

**Amperage**

Pump 1	L1 <input type="checkbox"/>	L2 <input type="checkbox"/>	L3 <input type="checkbox"/>	Pump 2	L1 <input type="checkbox"/>	L2 <input type="checkbox"/>	L3 <input type="checkbox"/>
Compressor 1	L1 <input type="checkbox"/>	L2 <input type="checkbox"/>	L3 <input type="checkbox"/>	Compressor 2	L1 <input type="checkbox"/>	L2 <input type="checkbox"/>	L3 <input type="checkbox"/>
Cond. fan 1	L1 <input type="checkbox"/>	L2 <input type="checkbox"/>	L3 <input type="checkbox"/>	Cond. fan 2	L1 <input type="checkbox"/>	L2 <input type="checkbox"/>	L3 <input type="checkbox"/>
Cond. fan 3	L1 <input type="checkbox"/>	L2 <input type="checkbox"/>	L3 <input type="checkbox"/>	Cond. fan 4	L1 <input type="checkbox"/>	L2 <input type="checkbox"/>	L3 <input type="checkbox"/>

**Mechanical**

Compressor 1 model #	Serial #
Compressor 1 oil level	Empty <input type="checkbox"/> 1/4 <input type="checkbox"/> 1/2 <input type="checkbox"/> 3/4 <input type="checkbox"/>
Compressor 2 model #	Serial #
Compressor 2 oil level	Empty <input type="checkbox"/> 1/4 <input type="checkbox"/> 1/2 <input type="checkbox"/> 3/4 <input type="checkbox"/>

KKT chillers, Inc.  
1280 Landmeier Road, Elk Grove Village, IL 60007  
T: 847 734 1800 | F: 847 734 1801 | E: sales@kkt-chillersusa.com | W: www.kkt-chillersusa.com

Revision: V01.3 Page 1 of 2 Effective Date: 06.16.15 Revised: 05.03.17

☐ Startup  
☐ Preventative Maintenance  
☐ Service Work Order

**KKT chillers**

**Attention:** To avoid site issues, never turn off chiller without prior permission from site personnel.

**Mechanical (continued)**

Pump 1 Make / Model	Serial #		
Type of glycol	Propylene <input type="checkbox"/>	Ethylene <input type="checkbox"/>	Percentage <input type="checkbox"/>
Water	Deionized <input type="checkbox"/>	Tap Water <input type="checkbox"/>	
Pump 2 Make / Model	Serial #		
Type of glycol	Propylene <input type="checkbox"/>	Ethylene <input type="checkbox"/>	Percentage <input type="checkbox"/>
Water	Deionized <input type="checkbox"/>	Tap Water <input type="checkbox"/>	

**Pressure**

Pump 1	Suction	Discharge	Static Pressure (Must be measured with chiller off)
Pump 2	Suction	Discharge	* ECO / Modbus Units (Measure at R/P)
Compressor 1	Suction	Discharge	* Generation 1 (Measure at Chiller Pump)
Compressor 2	Suction	Discharge	Nitrogen pressure (Startup or when using Buffer Tank ECO only)

No.	Description	Circuit 1	Circuit 2
1	Condensing outlet temperature	<input type="text"/>	<input type="text"/>
2	Liquid temperature	<input type="text"/>	<input type="text"/>
3	Subcooling	<input type="text"/>	<input type="text"/>
4	Evaporation outlet temperature	<input type="text"/>	<input type="text"/>
5	Suction gas temperature	<input type="text"/>	<input type="text"/>
6	Superheat	<input type="text"/>	<input type="text"/>

Ambient temperature:  °C  
Coolant temperature:  °C

**Notes:** Above readings must be taken while chiller is operating against a heat load.

**Comments**

**Attention:** Please check with site personnel when work is complete, and reset any equipment that may have faulted during service.

Check In Date / Time:  Check Out Date / Time:  Follow-up required? ☐ Yes ☐ No

Customer Signature:  Date:

Please return the completed form to KKT chillers: [techsupport@kktchillersusa.com](mailto:techsupport@kktchillersusa.com)

KKT chillers, Inc.  
1280 Landmeier Road, Elk Grove Village, IL 60007  
T: 847 734 1800 | F: 847 734 1801 | E: sales@kkt-chillersusa.com | W: www.kkt-chillersusa.com

Revision: V01.3 Page 2 of 2 Effective Date: 06.16.15 Revised: 05.03.17